

Project Evaluation

Project Log # 200706083

Preliminary Evaluation of 14 Roundabout Installations

Documents Prepared By:

Safety Evaluation Group
Traffic Safety Systems Management Section
Traffic Engineering and Safety Systems Branch
North Carolina Department of Transportation

Principal Investigator



Carrie L. Simpson, PE

Traffic Safety Project Engineer

9/18/2007
Date

PROJECT INFORMATION AND BACKGROUND

A statewide listing of roundabout installation locations was obtained from the Congestion Management Section. Note that this was not necessarily an all-inclusive listing but contained all known locations at the time. It contained 37 roundabout locations, which were built between 1999 through 2006. Three of the locations were under private jurisdiction and were removed from the list because we could not obtain crash data. The remaining 34 roundabout locations are listed below in Table 1.

Seventeen locations contained enough after period data to perform a preliminary countermeasure evaluation. Note that three of these locations could not be evaluated (see *italicized* locations) because either the intersection did not exist prior to the roundabout installation or one of the legs was removed in the after period. The remaining 14 roundabout locations with greater than 3 years of after period crash data have been evaluated to provide preliminary results. All roundabout locations with less than three years of after period crash data will be evaluated in the future *Final Report* when enough after period data becomes available.

TABLE 1. STATEWIDE LISTING OF ROUNDABOUT LOCATIONS

Locations For Preliminary Evaluation: Greater Than Three Years of After Period Crash Data Available

Built	Div	County	Municipality	Location	Jurisdiction	Description
1999	9	Forsyth	Clemmons	Fraternity Church at Hope Church	State	New School Drive
2000	5	Durham	Durham	Washington at Glendale	Muni	Modified Circle, Part of I-85 Detour Route
2000	9	Forsyth	Lewisville	Williams at US 421 SB Ramps	State	Solved Capacity Problem
2000	10	Mecklenburg	Charlotte	Ninth at Davidson	Muni	
2001	2	Craven	New Bern	Broad at E. Front *	State	Part of Enhancement Project
2001	9	Forsyth	Winston-Salem	Westview at Buckingham	Muni	City - Possible Traffic Calming Location
2002	9	Davie	Advance	NC 801 at I-40 EB Ramp	State	Developer - "Temporary" Intersection Fix
2002	9	Forsyth	Bethania	Turfwood at Long Creek *	State	Developer
2002	9	Forsyth	Lewisville	Styers Ferry at Utility	State	
2002	11	Wilkes		Yellowbanks at Haymeadow	State	Spot Safety
2002	13	Buncombe	Asheville	Lake at Mountain	State	Developer
2002	13	Buncombe	Asheville	WT Weaver at University Heights	State	City / University Project
2003	1	Dare	Kill Devil Hills	Veterans at Sixth *	Muni	Built For New High School Drive
2003	5	Durham	Durham	NC 751 at Old Erwin	State	Spot Safety
2003	5	Wake	Raleigh	Pullen at Stinson	Muni	
2003	9	Forsyth	Lewisville	Williams at US 421 NB Ramps	State	"Mirror" Image Of Other Ramp
2003	10	Mecklenburg	Charlotte	Park at Tremont	Muni	City - Possible Traffic Calming Location

Future Locations to Be Evaluated: Less Than Three Years of After Period Crash Data Available

Built	Div	County	Municipality	Location	Jurisdiction	Description
2004	10	Mecklenburg	Charlotte	Shopton Road	State	Developer
2004	10	Mecklenburg	Huntersville	Stumptown Road	State	Developer
2004	14	Haywood	Waynesville	US 23B	State	TIP Project
2004	14	Polk	Columbus	I-26 SB Ramp at NC 108	State	Interchange - Two Lane Bridge

Future Locations to Be Evaluated: Less Than Two Years of After Period Crash Data Available

Built	Div	County	Municipality	Location	Jurisdiction	Description
2005	5	Durham	Durham	Woodcroft at Highgate	Muni	City Safety Project, In Lieu Of Signal
2005	5	Durham	Chapel Hill	Ephesus Church at Pope	State	Developer Design / Build, Has Geometric Issues
2005	8	Moore	Southern Pines	Knoll Road	State	
2005	9	Forsyth	Winston-Salem	Old Salem/ Main at Salem	State	TIP Project U-2926 - Multilane
2005	10	Mecklenburg	Charlotte	Moore's Chapel at I-485 NB Ramp	State	Roundabout Interchange - I-485 Not Open Yet
2005	10	Mecklenburg	Charlotte	Moore's Chapel at I-485 SB Ramp	State	Roundabout Interchange - I-485 Not Open Yet
2005	12	Gaston	Gastonia	Gaston Day School Road	State	Safety Problem - Did Not Meet Signal Warrants
2005	13	Buncombe	Asheville	College at Oak	Muni	Downtown Redevelopment - Road "Diet"

Future Locations to Be Evaluated: Less Than One Year of After Period Crash Data Available

Built	Div	County	Municipality	Location	Jurisdiction	Description
2006	5	Wake	Wake Forest	NC 98 at US 1A	State	Moving Ahead Project
2006	10	Mecklenburg	Davidson	Griffith at Davidson Gateway	State	Developer - Multilane Existing Intersection
2006	10	Mecklenburg	Davidson	Griffith at Jetton	State	Developer - Multilane Existing Intersection
2006	10	Stanly	Norwood	Cottonville at South Stanly School	State	
2006	14	Polk	Columbus	I-26 NB Ramp at NC 108	State	Interchange - Two Lane Bridge

*Could not evaluate due to the addition (or removal) of an intersection leg in the after period.

LOCATIONS FOR PRELIMINARY EVALUATION

The 14 roundabout locations with greater than 3 years of after period were divided into 3 groups by intersection characteristics. Group 1 consists of the roundabout locations with a mainline speed limit at or below 35 mph, and stop sign control in the before period. Group 2 consists of the roundabout locations with a mainline speed limit above 35 mph, and stop sign control in the before period. Group 3 (which contains only one location) consists of the roundabout locations with a mainline speed limit at or below 35 mph, and signalized control in the before period.

The roundabout locations contain a mix of rural and urban environments. A majority of sites have four intersection legs, although several have three intersection legs. Because field reviews were not performed prior to the preliminary evaluation, the speed limits were based on the TEAAS ordinance system where available. Where unavailable, crash reports were used to obtain the intersection approach speed limits. Field reviews will be performed prior to the final evaluation to confirm data.

Please see the *Appendices* for a location map and site photos obtained from the Congestion Management Section.

TABLE 2. LISTING OF ROUNDABOUT LOCATIONS FOR PRELIMINARY EVALUATION

Group 1. Mainline Speed Limit At or Below 35 mph (Prior Control - Stop Sign)								Speed Limit	
Div	County	Municipality	Location	Built	Prior Control	Setting	# Legs	Major Rd	Minor Rd
5	Wake	Raleigh	Pullen at Stinson	2003	Stop	Urban	4	25	25
10	Mecklenburg	Charlotte	Park at Tremont	2003	Stop	Urban	4	25	25
5	Durham	Durham	Washington at Glendale	2000	Stop	Urban	4	35	35
9	Forsyth	Winston-Salem	Westview at Buckingham	2001	Stop	Urban	4	35	35
13	Buncombe	Asheville	WT Weaver at University Heights	2002	Stop	Urban	3	35	35
9	Davie	Advance	NC 801 at I-40 EB Ramp	2002	Stop	Rural	4	35*	70 (Ramp)
13	Buncombe	Asheville	Lake at Mountain	2002	Stop	Rural	3	35	35

Group 2. Mainline Speed Limit Above 35 mph (Prior Control - Stop Sign)								Speed Limit	
Div	County	Municipality	Location	Built	Prior Control	Setting	# Legs	Major Rd	Minor Rd
9	Forsyth	Lewisville	Styers Ferry at Utility	2002	Stop	Rural	4	45	45
9	Forsyth	Lewisville	Williams at US 421 SB Ramps	2000	Stop	Rural	4	45*	50*/ 65 (Ramp)
9	Forsyth	Lewisville	Williams at US 421 NB Ramps	2003	Stop	Rural	4	45*	65 (Ramp)
5	Durham	Durham	NC 751 at Old Erwin	2003	Stop	Rural	3	55	45
9	Forsyth	Clemmons	Fraternity Church at Hope Church	1999	Stop	Rural	4	55	55
11	Wilkes	N/A	Yellowbanks at Haymeadow	2002	Stop	Rural	4	55	55

Group 3. Mainline Speed Limit At or Below 35 mph (Prior Control - Signal)								Speed Limit	
Div	County	Municipality	Location	Built	Prior Control	Setting	# Legs	Major Rd	Minor Rd
10	Mecklenburg	Charlotte	Ninth at Davidson	2000	Signal	Urban	4	35	35

* Speed limits based on TEAAS ordinances.

RESULTS

The following tables provide location and crash information for each of the treatment sites. Tables 3, 6, and 9 provide a listing of before and after crash data at each site. The treatment data consisted of all crashes within 150 feet of the treatment intersections. Please see the *Appendices* for the before and after collision diagrams provided at each location.

The analysis periods for the treatment sites were between 3.17 years and 7.17 years. Because the installation dates varied from 1999 through 2003, the time periods for each location varied depending on when the roundabout was constructed. The ending dates for the analyses were determined by the available crash data at the time the crash analysis was completed. Due to limited knowledge of the installation dates, the entire year of installation was omitted from this analysis to provide an adequate construction period. Note that the before and after time periods consisted of an equal number of years at each location.

Tables 4 and 7 provide the aggregated naïve before and after analysis for Groups 1 and 2, respectively. Note that the value after the “+/-” notation in this evaluation indicates the standard deviation of an estimated value.

Tables 5 and 8 provide the aggregated before and after analysis with an adjustment for traffic volumes for Groups 1 and 2, respectively. This adjustment was provided to consider the effects of an increase in volume, which the naïve before and after analysis does not take into account. A linear assumption was made to account for the increase in traffic volumes.

Group 1. Mainline Speed Limit At or Below 35 mph (Prior Control - Stop Sign)

TABLE 3. GROUP 1 CRASH DATA

Div	County	Municipality	Location	Built	Years	Before		After		Percent Increase (+)/
						AADT	Total Crashes	AADT	Total Crashes	Percent Decrease (-)
5	Wake	Raleigh	Pullen at Stinson	2003	3.17	11000	12	12500	3	-75.0%
10	Mecklenburg	Charlotte	Park at Tremont	2003	3.17	7200	4	6000	4	0.0%
5	Durham	Durham	Washington at Glendale	2000	6.17	5500	4	5500	5	25.0%
9	Forsyth	Winston-Salem	Westview at Buckingham	2001	5.17	7400	6	6000	0	-100.0%
13	Buncombe	Asheville	WT Weaver at University Heights	2002	4.17	3000	10	3800	3	-70.0%
9	Davie	Advance	NC 801 at I-40 EB Ramp	2002	4.17	9000	12	16800	13	8.3%
13	Buncombe	Asheville	Lake at Mountain	2002	4.17	2000	0	2400	1	N/A

TABLE 4. GROUP 1 NAÏVE BEFORE AND AFTER ANALYSIS

	Estimates of Parameters
Actual Number of After Period Crashes, λ	29 +/- 5
Predicted Number of After Period Crashes, π	48 +/- 7
Index of Effectiveness, θ	0.59 +/- 0.14
Percent Increase (+)/ Percent Decrease (-)	-41% +/- 14%

TABLE 5. GROUP 1 BEFORE AND AFTER ANALYSIS WITH TRAFFIC ADJUSTMENT

	Estimates of Parameters
Actual Number of After Period Crashes, λ	29 +/- 5
Predicted Number of After Period Crashes, π	61 +/- 10
Index of Effectiveness, θ	0.46 +/- 0.11
Percent Increase (+)/ Percent Decrease (-)	-54% +/- 11%

For Group 1 Locations, the results of the naïve before and after analysis yield a 41% (+/- 14%) reduction in total crashes. Also, the results of the before and after analysis with consideration for traffic increase yielded a 54% (+/- 11%) reduction in total crashes.

Group 2. Mainline Speed Limit Above 35 mph (Prior Control - Stop Sign)

TABLE 6. GROUP 2 CRASH DATA

Div	County	Municipality	Location	Built	Years	Before		After		Percent Increase (+)/
						AADT	Total Crashes	AADT	Total Crashes	Percent Decrease (-)
9	Forsyth	Lewisville	Styers Ferry at Utility	2002	4.17	4500	2	5000	2	0.0%
9	Forsyth	Lewisville	Williams at US 421 SB Ramps	2000	6.17	12900	11	14200	3	-72.7%
9	Forsyth	Lewisville	Williams at US 421 NB Ramps	2003	3.17	12500	4	13600	6	50.0%
5	Durham	Durham	NC 751 at Old Erwin	2003	3.17	16100	14	15600	2	-85.7%
9	Forsyth	Clemmons	Fraternity Church at Hope Church	1999	7.17	2200	0	4400	2	N/A
11	Wilkes		Yellowbanks at Haymeadow	2002	4.17	3600	4	2900	4	0.0%

TABLE 7. GROUP 2 NAÏVE BEFORE AND AFTER ANALYSIS

										Estimates of Parameters
Actual Number of After Period Crashes, λ										19 +/- 4
Predicted Number of After Period Crashes, π										35 +/- 6
Index of Effectiveness, θ										0.53 +/- 0.15
Percent Increase (+)/ Percent Decrease (-)										-47% +/- 15%

TABLE 8. GROUP2 BEFORE AND AFTER ANALYSIS WITH TRAFFIC ADJUSTMENT

										Estimates of Parameters
Actual Number of After Period Crashes, λ										19 +/- 4
Predicted Number of After Period Crashes, π										36 +/- 6
Index of Effectiveness, θ										0.52 +/- 0.15
Percent Increase (+)/ Percent Decrease (-)										-48% +/- 15%

For Group 2 Locations, the results of the naïve before and after analysis yield a 47% (+/- 15%) reduction in total crashes. Also, the results of the before and after analysis with consideration for traffic increase yielded a 48% (+/- 15%) reduction in total crashes.

Group 3. Mainline Speed Limit At or Below 35 mph (Prior Control - Signal)

TABLE 9. GROUP 3 CRASH DATA

Div	County	Municipality	Location	Built	Years	Before		After		Percent Increase (+)/
						AADT	Total Crashes	AADT	Total Crashes	Percent Decrease (-)
10	Mecklenburg	Charlotte	Ninth at Davidson	2000	6.17	20500	31	19500	8	-74.2%

The single location in Group 3 experienced a 74% reduction in total crashes. Hopefully, in the *Final Report*, we will be able to utilize more locations with prior signalized control. Then we will be able to provide a more accurate estimate of the crash reductions for this group.

CONCLUSIONS

The preliminary evaluation of roundabout installations resulted in the following crash reduction factors:

Group 1. Mainline Speed Limit At or Below 35 mph (Prior Control – Stop Sign)

Total Crashes Using Naïve Before and After Analysis: **-41% +/- 14%**

Total Crashes Using Before and After Analysis With Traffic Adjustment: **-54% +/- 11%**

Group 2. Mainline Speed Limit Above 35 mph (Prior Control - Stop Sign)

Total Crashes Using Naïve Before and After Analysis: **-47% +/- 15%**

Total Crashes Using Before and After Analysis With Traffic Adjustment: **-48% +/- 15%**

Also, the single location in Group 3 (with Prior Control – Signal) experienced a 74% reduction in total crashes. The preliminary results demonstrate that all three groups of roundabout locations appear to have had a substantial reduction in the frequency of crashes from the before to the after period.

In addition to our preliminary study results, previous research has also shown that roundabouts may improve the safety of intersections. The crash reductions resulting from roundabout installations may be attributed to eliminating or altering conflict types, reducing speed differentials at intersections, and forcing drivers to decrease speeds as they proceed into and through the intersection. Roundabouts reduce vehicular crossing conflicts, thus diminishing the opportunity for Frontal Impact crashes to occur. The reduction of conflicts through the physical and geometric features of a roundabout have been shown to be more effective than the separation of conflicts by time as in a signalized intersection.

Please note that this is a preliminary evaluation based only on the current available data. This evaluation will be updated when there is at least three years of after data available at the remaining locations, so a more concrete conclusion can be drawn. At that time we will be able to provide more objective and definite information regarding actual crash reduction factors.

REFERENCES

1. Federal Highway Administration. Roundabouts: An Informational Guide. FHWA-RD-00-67, Washington, D.C., 2000.
2. Persaud, B.N., R.A. Retting, P.E. Garder, and D. Lord. Crash Reductions Following Installation of Roundabouts in the United States. Insurance Institute for Highway Safety, Arlington, VA, 2000.

--

Please direct questions or comments on this evaluation to Carrie Simpson, PE at (919) 662-4607 or via email at clsimpson@dot.state.nc.us.

APPENDICES

A) Location Map

B) Location Photos and Collision Diagrams

- Group 1
- Group 2
- Group 3

Appendix A. Location Map

LOCATION MAP: Roundabout Locations for Preliminary Evaluation

- Group 1. Seven Locations with Mainline Speed Limit At or Below 35 mph (Prior Control - Stop Sign)
- Group 2. Six Locations with Mainline Speed Limit Above 35 mph (Prior Control - Stop Sign)
- Group 3. One Location with Mainline Speed Limit At or Below 35 mph (Prior Control - Signal)



Appendix B. Location Photos and Collision Diagrams

GROUP 1

Pullen at Stinson



PULLEN RD AT STINSON DR

WAKE CO.

NOVEMBER 1, 1999 - DECEMBER 31, 2002


(3.17 YRS)

BEFORE PERIOD - TOTAL CRASHES

PULLEN RD

PULLEN PARK THEATRE

LEGEND




25 mph

STINSON DR

25 mph

PULLEN RD
25 mph

TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 5	REGION: CAPITAL
		STUDY PERIOD: 11/01/99 - 12/31/02	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF PULLEN RD AT STINSON DR		DATE:	08/13/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

PULLEN RD AT STINSON DR
 WAKE CO.
 JANUARY 1, 2004 - FEBRUARY 28, 2007
 (3.17 YRS)
 AFTER PERIOD - TOTAL CRASHES

PULLEN RD
 25 mph

STINSON DR.


PULLEN PARK THEATRE DR

25 mph

25 mph

PULLEN DR
 25 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT HIGHWAY SAFETY IMPROVEMENT PROGRAM		SAFETY INFORMATION MANAGEMENT AND SUPPORT	
		COLLISION DIAGRAM	
		DIVISION: 5	REGION: CAPITAL
		STUDY PERIOD: 01/01/04 - 02/28/07	
		ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION INTERSECTION OF PULLEN RD AT STINSON DR		SCALE: NOT TO SCALE DATE: 08/14/2007 LOG NUMBER: 200706083 PAGE: 1 OF 1	
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

Park at Tremont



PARK RD AT TREMONT AVE

MECKLENBURG CO.

NOVEMBER 1, 1999 - DECEMBER 31, 2002

(3.17 YRS)

BEFORE PERIOD - TOTAL CRASHES



25 mph

E TREMONT AVE



PARK RD


BROOKSIDE AVE



PARK RD

25 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 10	REGION: METRO
		STUDY PERIOD: 11/01/99 - 12/31/02	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF PARK RD AT TREMONT AVE		DATE:	08/13/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			


PARK RD AT TREMONT AVE

MECKLENBURG CO.

JANUARY 1, 2004 - FEBRUARY 28, 2007

(3.17 YRS)

AFTER PERIOD - TOTAL CRASHES



LEGEND

	MOVING VEHICLE		ANGLE		9 MPH OR LESS		P PEDESTRIAN
	PEDESTRIAN		TURNING		10 MPH TO 19		B BICYCLE
	PAKED VEHICLE		BACKING		20 MPH TO 29		T TRAIN
	PARKING VEHICLE		SIDESWIPE		30 MPH TO 39		A ANIMAL
	FIXED OBJECT		OUT OF CONTROL		40 MPH TO 49		VEHICLE FIRE
	HEAD ON		INJURY		50 MPH TO 59		DRIVER AT FAULT
	REAR END		FATALITY		60 MPH TO 69		D DRY
	RAN OFF ROAD				70 AND UP		W WET
					SPEED UNKNOWN		DAYLIGHT CRASH
					DARK CRASH		I ICY OR SNOWY

TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM		SAFETY INFORMATION MANAGEMENT AND SUPPORT	
		DIVISION: 10	REGION: METRO
		STUDY PERIOD: 01/01/04 - 02/28/07	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION		TRAFFIC SAFETY	
INTERSECTION OF PARK RD AT TREMONT AVE		SCALE:	NOT TO SCALE
		DATE:	08/14/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION			
DIVISION of HIGHWAYS			
TRAFFIC ENGINEERING AND SAFETY			
SYSTEMS BRANCH			

Washington at Glendale




GLENDALE AVE. AT WASHINGTON ST


DURHAM CO.

NOVEMBER 1, 1993 - DECEMBER 31, 1999
(6.17 YRS)

BEFORE PERIOD - TOTAL CRASHES



LEGEND




TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 5	REGION: CAPITAL
		STUDY PERIOD: 11/01/93 - 12/31/99	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION		TRAFFIC SAFETY	SCALE: NOT TO SCALE
INTERSECTION OF GLENDALE AVE. AT WASHINGTON ST		DATE: 08/28/2007	LOG NUMBER: 200706083
		PAGE: 1	OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			


GLENDALE AVE. AT WASHINGTON ST

DURHAM CO.

JANUARY 1, 2001 - FEBRUARY 28, 2007
(6.17 YRS)

AFTER PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT			
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT		
			
		COLLISION DIAGRAM	
		DIVISION: 5	REGION: CAPITAL
		STUDY PERIOD: 01/01/01 - 02/28/07	
ANALYSIS PREPARED BY: CLS			
DIAGRAM PREPARED BY: TSF			
DIAGRAM REVIEWED BY: CLS			
SAFETY EVALUATION			
TRAFFIC SAFETY			
INTERSECTION OF GLENDALE AVE. AT WASHINGTON ST.			

SCALE: NOT TO SCALE
DATE: 8/24/2007
LOG NUMBER: 200706083
PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

Westview at Buckingham



WESTVIEW DR AT BUCKINGHAM DR

FORSYTH CO.

NOVEMBER 1, 1995 - DECEMBER 31, 2000

(5.17 YRS)

BEFORE PERIOD - TOTAL CRASHES

WESTVIEW DR.

35 mph



BUCKINGHAM DR.

35 mph

BUCKINGHAM DR.




35 mph

35 mph

WESTVIEW DR.

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT

HIGHWAY SAFETY IMPROVEMENT PROGRAM

SAFETY INFORMATION MANAGEMENT AND SUPPORT



SAFETY EVALUATION

TRAFFIC SAFETY

INTERSECTION OF WESTVIEW DR.
AT BUCKINGHAM DR.

COLLISION DIAGRAM

DIVISION: 9 REGION: TRIAD

STUDY PERIOD: 11/01/95 - 12/31/00

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

DATE: 08/24/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

WESTVIEW DR. AT BUCKINGHAM DR.

FORSYTH CO.

JANUARY 1, 2002 - FEBRUARY 28, 2007

(5.17 YRS)

AFTER PERIOD - TOTAL CRASHES



35 mph

WESTVIEW DR.

35 mph



BUCKINGHAM DR.


BUCKINGHAM DR.



35 mph

WESTVIEW DR.


LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 9	REGION: TRIAD
		STUDY PERIOD: 01/01/02 - 02/28/07	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF WESTVIEW DR. AT BUCKINGHAM DR.		DATE:	8/24/2008
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

WT Weaver at University Heights



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT HIGHWAY SAFETY IMPROVEMENT PROGRAM		SAFETY INFORMATION MANAGEMENT AND SUPPORT	
		COLLISION DIAGRAM	
		DIVISION: 13	REGION: BLUE RIDGE
		STUDY PERIOD: 11/01/97 - 12/31/01	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
SAFETY EVALUATION		TRAFFIC SAFETY	
INTERSECTION OF WT WEAVER BLVD AT UNIVERSITY HEIGHTS			
		SCALE:	NOT TO SCALE
		DATE:	09/04/2006
		LOG NUMBER:	200602154
		PAGE:	1 OF 1
<p align="center"> N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH </p>			

W. T. WEAVER BLVD AT UNIVERSITY HEIGHTS

BUNCOMBE CO.

JANUARY 1, 2003 - FEBRUARY 28, 2007

(4.17 YRS)

AFTER PERIOD - TOTAL CRASHES

UNIVERSITY HEIGHTS

W. T. WEAVER BLVD



W. T. WEAVER BLVD

35 mph

35 mph

35 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT
HIGHWAY SAFETY IMPROVEMENT PROGRAM



SAFETY EVALUATION

TRAFFIC SAFETY

INTERSECTION OF W. T. WEAVER BLVD
AT UNIVERSITY HEIGHTS

COLLISION DIAGRAM

DIVISION: 13 REGION: BLUE RIDGE

STUDY PERIOD: 11/1/03 - 2/28/07

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

DATE: 9/04/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

NC 801 at I-40 EB Ramp




NC 801 AT I-40 EB RAMPS

DAVIE CO.

NOVEMBER 1, 1997 - DECEMBER 31, 2001

(4.17 YRS)

BEFORE PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT
HIGHWAY SAFETY IMPROVEMENT PROGRAM



SAFETY EVALUATION

TRAFFIC SAFETY

INTERSECTION OF NC 801
AT I-40 EB RAMPS

COLLISION DIAGRAM

DIVISION: 9 REGION: TRIAD

STUDY PERIOD: 11/01/97 - 12/31/01

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

DATE: 09/04/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

NC 80I AT I-40 EB RAMPS

DAVIE CO.

JANUARY 1, 2003 - FEBRUARY 28, 2007


(4.17 YRS)

AFTER PERIOD - TOTAL CRASHES

NC 80I


35 mph

LEGEND



I-40 EB OFF RAMP

I-40 EB ON RAMP



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT
SAFETY EVALUATION	
TRAFFIC SAFETY	
INTERSECTION OF NC 80I AT I-40 EB RAMPS	

COLLISION DIAGRAM	
DIVISION: 9	REGION: TRIAD
STUDY PERIOD: 01/01/03 - 02/28/07	
ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF	
DIAGRAM REVIEWED BY: CLS	
SCALE:	NOT TO SCALE
DATE:	8/20/2006
LOG NUMBER:	200706083
PAGE:	1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

Lake at Mountain



LAKE RD AT MOUNTAIN DR

BUNCOMBE CO.

NOVEMBER 1, 1997 - DECEMBER 31, 2001
(4.17 YRS)

BEFORE PERIOD - TOTAL CRASHES

SR 3437

35 mph




SR 3533
MOUNTAIN DR

35 mph

SR 3437
LAKE RD
CASE COVE RD

35 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 13	REGION: BLUE RIDGE
		STUDY PERIOD: 11/01/97 - 12/31/01	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF SR 3533 MOUNTAIN DR. AT SR 3437 LAKE RD		DATE:	08/31/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

LAKE RD AT MOUNTAIN DR

BUNCOMBE CO.

JANUARY 1, 2003 - FEBRUARY 28, 2007

(4.17 YRS)

AFTER PERIOD - TOTAL CRASHES



SR 3437
LAKE RD
35 mph


SR 3437

SR 3437

SR 3533
MOUNTAIN DR

35 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT



SAFETY EVALUATION
INTERSECTION OF SR 3533 MOUNTAIN DR.
AT SR 3437 LAKE RD

COLLISION DIAGRAM

DIVISION: 13	REGION: BLUE RIDGE
STUDY PERIOD: 01/01/02 - 02/28/07	
ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF	
DIAGRAM REVIEWED BY: CLS	
SCALE:	NOT TO SCALE
DATE:	8/31/2007
LOG NUMBER:	200706083
PAGE:	1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

GROUP 2

Styers Ferry at Utility



STYERS FERRY AT UTILITY

FORSYTH CO.

NOVEMBER 1, 1997 - DECEMBER 31, 2001
(4.17 YRS)


BEFORE PERIOD - TOTAL CRASHES

SHOPPING CENTER
ENTRANCE



UTILITY RD



LEGEND



SR 1100 STYERS FERRY RD



45 mph

1



2

45 mph

45 mph

SR 1100
STYERS FERRY RD

TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT
HIGHWAY SAFETY IMPROVEMENT PROGRAM



SAFETY EVALUATION

TRAFFIC SAFETY

INTERSECTION OF SR 1100 STYERS FERRY
AT UTILITY

COLLISION DIAGRAM

DIVISION: 9 REGION: TRIAD

STUDY PERIOD: 11/01/03 - 12/31/2001

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

DATE: 08/29/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH


STYERS FERRY AT UTILITY FORSYTH CO.

JANUARY 1, 2003 - FEBRUARY 28, 2007
(4.17 YRS)

AFTER PERIOD - TOTAL CRASHES

SHOPPING CENTER
ENTRANCE

LEGEND



SR 1100 STYERS FERRY RD

UTILITY RD

45 mph

45 mph

SR 1100
STYERS FERRY RD

45 mph

TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 9	REGION: TRIAD
		STUDY PERIOD: 01/01/03 - 02/28/07	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF SR 1100 STYERS FERRY AT UTILITY		DATE:	8/30/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

Williams Road at US 421 SB Ramps




WILLIAMS RD AT US 421-SB RAMPS

FORSYTH CO.

NOVEMBER 1, 1993 - DECEMBER 31, 1999
(6.17 YRS)

BEFORE PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT
SAFETY EVALUATION	
TRAFFIC SAFETY	
INTERSECTION OF US 421SB RAMPS AT WILLIAMS ROAD	

COLLISION DIAGRAM	
DIVISION: 9	REGION: TRIAD
STUDY PERIOD: 11/01/93 - 12/31/99	
ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF	
DIAGRAM REVIEWED BY: CLS	
SCALE:	
DATE:	08/28/2007
LOG NUMBER:	200706083
PAGE:	1 OF 1


N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

WILLIAMS RD AT US 42I-SB RAMPS

FORSYTH CO.

JANUARY 1, 2001 - FEBRUARY 28, 2007
(6.17 YRS)

AFTER PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT
SAFETY EVALUATION TRAFFIC SAFETY	
INTERSECTION OF US 42I SB RAMPS AT WILLIAMS ROAD	

COLLISION DIAGRAM	
DIVISION: 9	REGION: TRIAD
STUDY PERIOD: 01/01/01 - 02/28/07	
ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF	
DIAGRAM REVIEWED BY: CLS	
SCALE:	NOT TO SCALE
DATE:	8/28/2007
LOG NUMBER:	200706083
PAGE:	1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

Williams at US 421 NB Ramps



US 42I-NB RAMPS AT WILLIAMS RD

FORSYTH CO.

NOVEMBER 1, 1999 - DECEMBER 31, 2002
(3.17 YRS)

BEFORE PERIOD - TOTAL CRASHES




SR 1171
WILLIAMS RD

45 mph



65 mph



US 42I-NB/WB ON RAMP


65 mph



US 42I-NB/WB OFF RAMP

SR 1171
WILLIAMS RD
45 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT

HIGHWAY SAFETY IMPROVEMENT PROGRAM

SAFETY INFORMATION MANAGEMENT AND SUPPORT



SAFETY EVALUATION

TRAFFIC SAFETY

INTERSECTION OF US 42INB RAMPS
AT WILLIAMS ROAD

COLLISION DIAGRAM

DIVISION: 9 REGION: TRIAD

STUDY PERIOD: 11/01/99 - 12/31/02

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

DATE: 08/28/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

US 42I-NB RAMPS AT WILLIAMS RD

FORSYTH CO.

JANUARY 1, 2004 - FEBRUARY 28, 2007
(3.17 YRS)

AFTER PERIOD - TOTAL CRASHES



US 42I-NB/WB ON RAMP

65 mph

SR 1171
WILLIAMS RD

SR 1171
WILLIAMS RD
45 mph

US 42I-NB/WB OFF RAMP

65 mph

LEGEND

	MOVING VEHICLE		ANGLE		9 MPH OR LESS		P PEDESTRIAN
	PEDESTRIAN		TURNING		10 MPH TO 19		B BICYCLE
	PARKED VEHICLE		BACKING		20 MPH TO 29		T TRAIN
	FIXED OBJECT		SIDESWIPE		30 MPH TO 39		A ANIMAL
	HEAD ON		OUT OF CONTROL		40 MPH TO 49		VEHICLE FIRE
	REAR END		INJURY		50 MPH TO 59		DRIVER AT FAULT
	RAN OFF ROAD		FATALITY		60 MPH TO 69		D DRY
					70 AND UP		W WET
					SPEED UNKNOWN		DAYLIGHT CRASH
					DAYLIGHT CRASH		DARK CRASH
					DARK CRASH		ICY OR SNOWY

TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT

HIGHWAY SAFETY IMPROVEMENT PROGRAM



SAFETY EVALUATION

COLLISION DIAGRAM

DIVISION: 9 REGION: TRIAD

STUDY PERIOD: 01/01/04 - 02/28/07

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

INTERSECTION OF US 421NB/WB RAMPS
AT WILLIAMS ROAD

DATE: 8/28/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

NC 751 at Old Erwin



NC 751 AT OLD ERWIN RD

DURHAM CO.

NOVEMBER 1, 1999 - DECEMBER 31, 2002
(3.17 YRS)



BEFORE PERIOD - TOTAL CRASHES

SERVICE ROAD
FOR
DUKE FOREST

NC 751

NC 751

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT			
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT		
		COLLISION DIAGRAM	
		DIVISION: 5	REGION: CAPITAL
		STUDY PERIOD: 11/01/99 - 12/31/2002	
ANALYSIS PREPARED BY: CLS			
DIAGRAM PREPARED BY: TSF			
DIAGRAM REVIEWED BY: CLS			
SCALE: NOT TO SCALE			
DATE: 08/29/2007			
LOG NUMBER: 200706083			
PAGE: 1 OF 1			

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

NC 751 AT OLD ERWIN RD

DURHAM CO.

JANUARY 1, 2004 - FEBRUARY 28, 2007
(3.17 YRS)

AFTER PERIOD - TOTAL CRASHES

SERVICE ROAD
FOR
DUKE FOREST

NC 751


55 mph

55 mph

NC 751

SR 1307
OLD ERWIN RD
45 mph

LEGEND



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT

HIGHWAY SAFETY IMPROVEMENT PROGRAM

SAFETY INFORMATION MANAGEMENT AND SUPPORT



SAFETY EVALUATION

TRAFFIC SAFETY

INTERSECTION OF NC 751
AT OLD ERWIN ROAD

COLLISION DIAGRAM

DIVISION: 5 REGION: CAPITAL

STUDY PERIOD: 01/01/04 - 02/28/07

ANALYSIS PREPARED BY: CLS

DIAGRAM PREPARED BY: TSF

DIAGRAM REVIEWED BY: CLS

SCALE: NOT TO SCALE

DATE: 8/24/2007

LOG NUMBER: 200706083

PAGE: 1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH

Fraternity Church at Hope Church



FRATERNITY CHURCH AT HOPE CHURCH

FORSYTH CO.

NOVEMBER 1, 1991 - DECEMBER 31, 1998
(7.17 YRS)

BEFORE PERIOD - TOTAL CRASHES

SR 2979
HOPE CHURCH RD

SR 2991
FRATERNITY CHURCH RD





55 mph

55 mph

SR 2991
FRATERNITY CHURCH RD

LEGEND




TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: 9	REGION: TRIAD
		STUDY PERIOD: 11/01/91 - 12/31/1998	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF FRATERNITY CH ROAD AT HOPE CH ROAD		DATE:	08/29/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			


FRATERNITY CHURCH AT HOPE CHURCH

FORSYTH CO.

JANUARY 1, 2000 - FEBRUARY 28, 2007
(7.17 YRS)

AFTER PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM		SAFETY INFORMATION MANAGEMENT AND SUPPORT	
		DIVISION: 9	REGION: TRIAD
		STUDY PERIOD: 01/01/00 - 02/28/07	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
SAFETY EVALUATION		TRAFFIC SAFETY	
INTERSECTION OF FRATERNITY CH ROAD AT HOPE CH ROAD		SCALE:	NOT TO SCALE
		DATE:	8/30/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

Yellowbanks at Haymeadow – No Photos Available

YELLOW BANKS AT HAYMEADOW


WILKES CO.

NOVEMBER 1, 1997 - DECEMBER 31, 2001
(4.17 YRS)

BEFORE PERIOD - TOTAL CRASHES


SR 1716
HAYMEADOW RD
55 mph

LEGEND



SR 1716 YELLOW BANKS RD

SR 1713 YELLOW BANKS RD



55 mph

55 mph

SR 1707
HAYMEADOW CHURCH RD


TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: II	REGION: HIGH
		STUDY PERIOD: 11/01/97 - 12/31/2001	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF YELLOW BANKS AT HAYMEADOW		DATE:	08/29/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			


YELLOWBANKS AT HAYMEADOW

WILKES CO.

JANUARY 1, 2003 - FEBRUARY 28, 2007
(4.17 YRS)

AFTER PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT		COLLISION DIAGRAM	
HIGHWAY SAFETY IMPROVEMENT PROGRAM	SAFETY INFORMATION MANAGEMENT AND SUPPORT	DIVISION: II	REGION: HIGH
		STUDY PERIOD: 01/01/03 - 02/28/07	
		ANALYSIS PREPARED BY: CLS	
		DIAGRAM PREPARED BY: TSF	
		DIAGRAM REVIEWED BY: CLS	
SAFETY EVALUATION	TRAFFIC SAFETY	SCALE:	NOT TO SCALE
INTERSECTION OF YELLOW BANKS AT HAYMEADOW		DATE:	8/30/2007
		LOG NUMBER:	200706083
		PAGE:	1 OF 1
N.C. DEPARTMENT of TRANSPORTATION DIVISION of HIGHWAYS TRAFFIC ENGINEERING AND SAFETY SYSTEMS BRANCH			

GROUP 3

Ninth at Davidson




NINTH ST AT DAVIDSON ST

MECKLENBURG CO.


NOVEMBER 1, 1993 - DECEMBER 31, 1999
(6.17 YRS)


BEFORE PERIOD - TOTAL CRASHES



N DAVIDSON ST

E 9TH ST



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT	
<small>HIGHWAY SAFETY IMPROVEMENT PROGRAM</small> 	<small>SAFETY INFORMATION MANAGEMENT AND SUPPORT</small>
<small>SAFETY EVALUATION</small>	
INTERSECTION OF N DAVIDSON ST AT E 9TH ST	
<small>TRAFFIC SAFETY</small>	

COLLISION DIAGRAM	
DIVISION: 10	REGION: METRO
STUDY PERIOD: 11/01/93 - 12/31/1999	
ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF	
DIAGRAM REVIEWED BY: CLS	
SCALE:	NOT TO SCALE
DATE:	09/05/2007
LOG NUMBER:	200706083
PAGE:	1 OF 1



N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH


NINTH ST AT DAVIDSON ST

MECKLENBURG CO.

JANUARY 1, 2001 - FEBRUARY 28, 2007
(6.17 YRS)

AFTER PERIOD - TOTAL CRASHES



TRAFFIC SAFETY SYSTEMS MANAGEMENT UNIT	
HIGHWAY SAFETY	SAFETY INFORMATION
IMPROVEMENT PROGRAM	MANAGEMENT AND SUPPORT
	
SAFETY EVALUATION	
INTERSECTION OF N DAVIDSON ST AT E 9TH ST	

COLLISION DIAGRAM	
DIVISION: 10	REGION: METRO
STUDY PERIOD: 01/01/01 - 02/28/07	
ANALYSIS PREPARED BY: CLS	
DIAGRAM PREPARED BY: TSF	
DIAGRAM REVIEWED BY: CLS	
SCALE:	NOT TO SCALE
DATE:	9/5/2008
LOG NUMBER:	200706083
PAGE:	1 OF 1

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
TRAFFIC ENGINEERING AND SAFETY
SYSTEMS BRANCH